

									PB-CLINIC	c						
CKT NO.	LOAD DESCRIPTIONS			VOLTS	PHASE	kVA	CURRENT AMPERES		INVERSE TIME DELAY CIRCUIT BREAKER			FEEDER BRANCH CIRCUIT COPPER WIRE, THHN/THWN			CONDUIT SIZE	
	QTY.	Unit VA	Description	1	,		AB	ВС	CA	AT	AF	POLE	PHASE	NEUTRAL	EGC	
1	1	2760	2.0 HP, ACU	230	SINGLE	2.76	12.00			20	-	2	2-5.5 mm2 THHN/THWN	-	1-5.5 mm² THHN/THWN	15 mmØ PVC PIPE
2	1	360	2 x CONVENIENCE OUTLET	230	SINGLE	0.36	5.48			20	-	2	2-3.5 mm2 THHN/THWN	-	1-2.0 mm2 THHN/THWN	15 mmØ PVC PIPE
3	1	540	3 x CONVENIENCE OUTLET	230	SINGLE	0.54			2.35	20	-	2	2-3.5 mm2 THHN/THWN	-	1-2.0 mm2 THHN/THWN	15 mmØPVC PIPE
4	1	1440	8 x CON\ENIENCE OUTLET	230	SINGLE	1.44			6.26	20	-	2	2-3.5 mm2 THHN/THWN	-	1- 2.0 mm2 THHN/THWN	15 mmØPVC PIPE
5	1	1260	7 x CON\ENIENCE OUTLET	230	SINGLE	1.26		1.57		20	-	2	2-3.5 mm2 THHN/THWN	-	1-2.0 mm2 THHN/THWN	15 mmØPVC PIPE
6	1	2364	16 x DOWNLICHT + 1 x ORBIT FAN + 17 x LED LIGHT TUBE + 3 x EXHAUST FAN + 10 x CONVENIENCE OUTLET	230	SINGLE	2.36		10.28		60	-	2	2-14 mm2 THHN/THWN	-	1-8.0 mm2 THHN/THWN	20 mmØ PVC PIPE
7	1	3335	2.5 HP, ACU	230	SINGLE	3.34	14.50			20	-	2	2-5.5 mm2 THHN/THWN	-	1-5.5 mm2 THHN/THWN	15 mmØPVC PIPE
8	1	1840	1 HP, ACU	230	SINGLE	1.84	8.00			20	-	2	2-5.5 mm2 THHN/THWN	-	1-5.5 mm2 THHN/THWN	15 mmØ PVC PIPE
9	1	2160	12 x CONVENIENCE OUTLET + 1 x FLOOR RECEPTACLE	230	SINGLE	2.16			9.39	20	-	2	2-5.5 mm2 THHN/THWN	-	1-5.5 mm2 THHN/THWN	15 mm@PVC PIPE
10	1	1840	1.0 HP, ACU	230	SINGLE	1.84			8.00	30	-	2	2-5.5 mm2 THHN/THWN	-	1-5.5 mm2 THHN/THWN	15 mmØPVC PIPE
11	1	1587	0.75 HP, ACU	230	SINGLE	1.59		6.90		30	-	2	2-5.5 mm2 THHN/THWN	-	1-3.5 mm2 THHN/THWN	15 mmØ PVC PIPE
12	1	443	16 x DOWNLICHT + 3 x ORBIT FAN + 4 x LED LIGHT TUBE + 1 x EXHAUST FAN	230	SINGLE	0.44		1.93		15	-	2	2-3.5 mm2 THHN/THWN	-	1-2.0 mm2 THHN/THWN	15 mmØPVC PIPE
13	1	1840	1 HP, ACU	230	SINGLE	1.84	8.00			20	-	2	2-5.5 mm2 THHN/THWN	-	1-5.5 mm2 THHN/THWN	15 mmØ PVC PIPE
14	1	1840	1 HP, ACU	230	SINGLE	1.84	8.00			20	-	2	2-5.5 mm2 THHN/THWN	-	1-5.5 mm2 THHN/THWN	15 mmØPVC PIPE
		TO	TAL CURRENT IN EACH PHASE (AMPE	RES)			55.98	20.67	26.00							
			INCOMING FEEDER CONDU	CTOR & PRO	TECTION DETA	AILS				225	-	3	3-100 mm2 THHN/THWN	-	1-22.0 mm2 THHN/THWN	50 mmØ PVC PIP
TOTAL CURRENT IN AMPERES 102.65				COMPUTATIONS: SIZE OF INCOMING FEEDER AT 80% DEMAND FACTOR							SIZE OF FEE	DER PROTECT	ION AT 80% DEMAND FACTOR	1		
											IP = 250% HML + (1.732 x (125% of HCL + HØ) + 30) x DF					
TOTAL CONNECTED LOAD VA				IC = 1.25 x 12 + [(1.732 x (1.25 x 55.08 + 65.87) + 0] x 0.8							IP = 2.5 x 12 + [1732 x [1.25 x 55.08 + 65.87]] + 01 x 0.8					
				IC = 201.67 Amperes							IP = 210.67 Amperes					
				USE: 3-100 mm2 THHN/THWN, 1-22.0 mm2, Stranded, Copper, in 50 mm Ø PVC PPE						PE	USE; 250 AT, INVESE TIME, 230V, 3P					

CHECKED / REVIEWED BY:	UNDER THE DIRECT SUPERVISION OF :	SEAL	R.A. 9266 Section 33	PROJECT TITLE:	PROJECT OWNER:	DRAWING CONTENTS	DESIGNED BY: TANO	ISSUED FOR:	REVISIONS:		DRAWING NO.
			Drawing and specification and other contract documents signed, stamped or sealed, as instrument of service, are the intellectual properly and documents of the architect, whether the object for which they are	of MEDICAL AND DENTAL CLINIC TO PROPOSED SCHEDULE OF LOADS	EE481 EEK2414 CAFSTONE 1		DATE DRAFTED: 09-04-2024	OWNER'S APPROVAL	NO. DATE	DESCRIPTION	
							DATE UPDATED: 09-15-2024	AS-BUILT			
							DRAFTED BY: RAS OBISO	BIDDING			_
			made is executed or not, if shall be unlawful for any person to duplicate or to make copies of said				APPROVED BY:	■ BUILDING PERMIT			
			documents for use in the repetition of and for other projects of building, weither executed partly in whole, without the written consent of architect or author of said.					☐ CONSTRUCTION			
								ESTIMATE			1
			documents.	LOCATION: CEBU INSTITUTE OF TECHNOLOGY - UNIVERSIT				FABRICATION	PROJECT CODE:		